Public Works (1910) Department.

G.O., No. 170 I

DATED 31/5/1910.

The Notes
in this G.O. have been printed.

[Despatch Abstract.]

Inspection bungalow at Chittampatti, Madura Dt.

An estimate amounting to Rs 256 for adding a servants' godown to the outhouse attached to the —— sanctioned.

JB 1/6/10

[P. W. 9. 1,250—22-7-09.]

SCA/9 / Dr / Inds

Indexed. 8/6

Registered as No 2 of 1910-11 2.6.10.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

Government of Madras.

PUBLIC WORKS DEPARTMENT

IRRIGATION.
ACCOUNT.

Recd.	1910.	*Enclosures*
Regd.		*Spare copies*

G.O., No. 170 I., 31st May 1910.

Inspection bungalow at Chittampatti, Madura Division

An estimate amounting to Rs. 256 for adding a servants' godown to the out-house attached to the — sanctioned.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Irrigation.
Account.

Read—the following papers:—

I

Letter—from H. E. Clerk, Esq., Superintending Engineer, VI Circle.
To—the Chief Engineer for Irrigation.
Dated—Trichinopoly, the 19th March 1910.
No.—328 C.E.

With reference to your Circular Memo. No. 616, dated 23rd February 1905, I have the honour to forward herewith, for your approval and sanction of Government, plans and estimate for adding a servants' godown (as shown on plan No. 16 of 1910) to the out-house attached to the inspection bungalow at Chittampatti, an important centre in the tract irrigated by the IX branch channel of the Periyár system. The bungalow is very frequently occupied by inspecting officers and the existing accommodation consists of one room, two dressing and two bath rooms without any store room. The out building, which it is now proposed to extend, consists of two rooms, each measuring 10′ × 7′ 9″ with a verandah 5 feet in front, one of which is used as a kitchen and the other as a store room for keeping in the tools, etc., belonging to Public Works Department. An additional room to be used as a servants' godown is very necessary. The rates entered in the estimate are fair.

Enclosure.

Report to accompany the estimate for constructing an additional store shed in the Chittampatti rest-house compound.

	RS.
Amount of estimate	256

The estimate provides for constructing a store shed * in continuation of the existing store room and kitchen in the rest-house compound, Chittampatti, as want of space is much felt by inspecting officers.

* Servants' godown.

H.E.C.

As per plan attached the extension is on the same design as the existing building. This extra accommodation is necessary as at present store space is very limited.

J.M.M.P.
25-2-10.

The masonry work will be of coursed rubble in mud for superstructure and coursed rubble in mortar for basement and concrete in surki mortar for foundations.

The interior of the room will be plastered with mortar and the exterior pointed with mortar.

Flooring is of $\frac{3}{4}$ inch surki mortar over a layer of 6 inches of concrete. The woodwork for roofing will be well tarred and rafters to be used are palmyrah wood.

The roofing is of pan tiles over bamboo reepers with chunam bordered.

25*th February* 1910.

J. M. M. Parker,
Executive Engineer, Madura Division.

II

Note by the Chief Engineer for Irrigation, dated 26th April 1910.

The estimate is recommended for sanction.

C. A. Smith,
Chief Engineer for Irrigation.

Order—No. 170 I., dated 31st May 1910.

The following estimate is sanctioned :—

Divided head.
Irrigation.
42. Major Works (Working Expenses).
Periyár System.
I. Extensions and Improvements.
3. Distributaries.
C. Works.

Constructing a servants' godown to the out-house attached to the inspection bungalow at Chittampatti.

	RS.
Estimate	256

2. This sanction is registered as No. 21 I. of 1910-1911.

(True Extract.)

C. A. Smith,
Joint Secretary to Govt., P.W.D.,
Irrigation Branch.

To the Chief Engineer for Irrigation.
,, Superintending Engineer, VI Circle (with plan and estimate).
,, Examiner, Public Works Accounts.

Forwarded to the

(By Order.)

Deputy Registrar.

PUBLIC WORKS DEPARTMENT
(IRRIGATION BRANCH).

NOTES CONNECTED WITH G.O., NO. 170 I., DATED 31ST MAY 1910.

[SUBJECT.—*Estimate amounting to Rs.* 256 *for constructing a servants' godown to the outhouse attached to the inspection bungalow at Chittampatti, Madura district.*]

From the Superintending Engineer, VI Circle, dated 19*th March* 1910, *No.* 328 *C.E.*

Under Secretary—

For orders whether the estimate may be checked for sanction.

B.G.R.
24-3-10.

S.S.
24-3-10.

Chief Engineer for Irrigation—

Occupied six days a month by Public Works Department officer, and twelve days a month by other officers for orders.

Vide page 30 of G.O., No. 1119 W., dated 18th May 1906.

J. M. LACEY.
26-3-10.

The necessity for the extra room is due to the use of the present room as a tool shed. Estimate may be checked.

C. A. SMITH.
29-3-10.

The estimate has been checked. The rates agree with the current schedule of the division.

M.V.
19-4-10.

To Superintendent, Finance Section—

For draft order.

N.S.
19-4-10.

Under Secretary—

A draft order sanctioning the estimate is submitted. If approved, it may be circulated through Financial to the Honourable Member in charge of that department with reference to his note,* dated 20th August 1909.

**Vide* notes connected with G.O., No. 366 I., dated 8th September 1909.

T.S.R.
23-4-10.

M.A.
23-4-10.

Joint Secretary—

J.M.L.
26-4-10.

To the Hon'ble Mr. J. N. Atkinson, C.S.I., through Financial.

C.A.S.
26-4-10.

FINANCIAL DEPARTMENT.

The draft order may be accepted in Financial.

A.H.
29-4-10.

Chief Secretary—

C. REILLY.
3-5-10.

Honourable Member—

W. S. MEYER.
5-5-10.

Hon'ble Mr. M. Hammick, C.S.I., C.I.E.

J. N. A[TKINSON].
7-5-10.

May be accepted.

M. H[AMMICK].
9-5-10.

To the Public Works Department (Irrigation) u.o.

PUBLIC WORKS DEPARTMENT
(IRRIGATION BRANCH).

Under Secretary—

Submitted that the draft order may now issue.

G.V.
10-5-10.

M.S.V.
10-5-10.

Issue.

J.M.L.
14-5-10.

[Issued as G.O., No. 170 I., dated 31st May 1910.]

C. No. 1191 of '10

SUBJECT :— Estimate of Rs 256 for constructing a servant's godown to the outhouse attached to the Inspection Bungalow at Chittampatti, Madura Dt.

Current No. 4923
Passed on by:
19.5.10
R. K.
D. O.
Enc. 4 + 1 plan = 5

PUBLIC WORKS DEPARTMENT,

IRRIGATION BRANCH.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

From the Supg. Engr:, VI Circle, d/19.3.10, No. 328CE

Print

Print Report

3P

—

Note by the Chief Engineer for Irrigation.

The estimate is recommended for sanction.

Order. No. 170 I d/31.5.10.

The following estimate is sanctioned:—

Divided Head.

Irrigation.

42- Major Works (Working Expenses).

Periyar System.

I Extensions and Improvements.

3. Distributaries.

C. Works.

Constructing a servant's

2/ 4P

godown to the outhouse attached to the Inspection Bungalow at Chittampatti.

Estimate Rs 256.

2. This sanction is registered as No 21-I of 1910-1911.

[signature] 26.4.10
[initials]

[initials] 26/4/10
I

[initials] 23/4/10
[initials] 23.4.10

To
The Chief Engr: for Irrign:
The Supt Engr:, 6th Circle with plan and Este. MS Despd 4/6/10
" Examr, P.W. Accts. Despd 2/7/10

Ordinary Press

Print notes

3

Exr 19-5-10

ee-1—5
bols-1-4

1209

[illegible] 10/6